



Building for the Future

Construction and
Renovation of Sterile
Processing Facilities

Cynthia Hubbard

Building for the Future Construction and Renovation of Sterile Processing Facilities

Cynthia A. Hubbard, RN

This publication is intended to be a helpful information resource. It is not to be construed as an interpretation of AAMI standards, nor does it constitute legal or regulatory advice.

All AAMI standards, recommended practices, technical information reports, and other types of technical documents developed by AAMI are voluntary, and their application is solely within the discretion and professional judgment of the user of the document.

The views expressed in this publication do not represent the views of AAMI. Standards and information concerning the content of standards that the external author may include within this document is subject to change as a result of ballot and public review.

Published by
Association for the Advancement of Medical Instrumentation
4301 N. Fairfax Drive, Suite 301
Arlington, VA 22203-1633
www.aami.org

© 2013 by the Association for the Advancement of Medical Instrumentation

All Rights Reserved

Publication, reproduction, photocopying, storage, or transmission, electronically or otherwise, of all or any part of this document without the prior written permission of the Association for the Advancement of Medical Instrumentation is strictly prohibited by law. It is illegal under federal law (17 U.S.C. § 101, et seq.) to make copies of all or any part of this document (whether internally or externally) without the prior written permission of the Association for the Advancement of Medical Instrumentation. Violators risk legal action, including civil and criminal penalties, and damages of \$100,000 per offense. For permission regarding the use of all or any part of this document, contact AAMI at 4301 N. Fairfax Drive, Suite 301, Arlington, VA 22203-1633. Phone: +1-703-525-4890; Fax: +1-703-525-1067.

Printed in the United States of America

ISBN 1-57020-463-2

This is a preview. [Click here to purchase the full publication.](#)

Table of Contents

	<i>Page</i>
Dedication and Acknowledgments	vii
Foreword	ix
1. Introduction	1
2. Definitions and Abbreviations	3
3. New Construction	9
New Construction Versus Renovation	9
Trends Affecting Design	10
Evidence-Based Design	10
Sustainable Design	10
Lean Design	10
Integrated Design Process	11
Overview of the Planning Process	12
Strategic Planning	12
Facility Master Planning	12
Facility Assessment	12
Site Development	12
Functional Programming	12
Space Programming	13
Conceptual Design	14
Schematic Design	14
Design Development	15
Construction Documentation	15
Equipment Specifications	15
Value Analysis	16
Planning New Construction for Sterile Processing	16
Understanding the Organization's Vision	16
Creating the Sterile Processing Vision	16
Assessing the Sterile Processing Workload	19
Estimating Future Needs	22
Developing Supportive Relationships with Customers	24
Infection Prevention and Control	25

	<i>Page</i>
Managing the Design Process	27
Interface with Architects and Consultants	27
Design Considerations for Sterile Processing Areas	28
Ongoing Decision Making When Reality Clashes with the Ideal	40
Construction Interface	40
Occupancy Planning	40
Preparing the SPD Team	40
Joint Planning with Customers	40
Internal SPD Occupancy Planning	41
Staffing Assessment	42
Application of 5S Methodology	42
Project Management Tools	43
Development of the Movable Equipment Layout	43
Equipment Testing and Verification	45
Moving Day	45
4. Renovation Projects	47
Driving Forces	47
Infection Prevention and Control	48
Practical Application of the Infection Control Risk Assessment	48
Mold Prevention	49
Prevention of Cross-Contamination	50
Operational Issues	50
Planning Considerations	50
Successful Renovation in a Functional SPD	52
SPD Team Collaboration	55
Options for Maintaining SPD Operations	57
Reprocessing Outside the SPD	61
Sharing the Work Space of an Ambulatory Surgery Center	61
Outsourcing Sterile Processing	63
Renovation Coordination	64
Communications	64
Monitoring Progress	64
Final Cleaning	64
Adjusting to the New Environment	65
5. New Equipment Planning	67
Importance of Equipment Planning	67
Determining the SPD Equipment Mix	67
Materials Reprocessing Life Cycle	69
Water and Steam Quality	70
Water Quality	70
Steam Quality	74

	<i>Page</i>
Integrated Process Flow	75
Decontamination Equipment Planning	76
Options for Cleaning and Disinfection	76
Spaulding Classification System	76
Manufacturers' IFU	77
Ultrasonic Cleaning	77
Thermal (Hot Water) Disinfection	79
Chemical Disinfection	86
Sterilization Equipment Planning	88
Steam Sterilizers	88
Low-Temperature Sterilizers and Processors	91
Vendor Assistance, Product Selection, and Site Visits	97
Vendor Assistance	97
Product Selection	97
Site Visits	98
Specifications	98
The Importance of Properly Written Specifications	98
General Guidance	99
Functional Specifications	100
Technical Specifications	100
Installation Requirements	100
Training Requirements	100
Guarantees	100
Warranties and Service Agreements	100
Warranties	100
Service Agreements	101
Installation	102
Installation Inspection and Testing	102
Drawings and Specifications	102
Verification of Service and Utility Requirements	102
Installation by Manufacturers' Representatives	102
Testing and Acceptance Criteria for Mechanical Washers	103
Washing Equipment Qualification Testing	103
Detergent Delivery Systems	103
Cleaning Verification	104
Qualification Testing of Sterilizers	104
The Importance of Qualification Testing	104
Steam Sterilizers	104
Low-Temperature Sterilizers and Processors	106

	<i>Page</i>
Staff Development and Training	106
Introduction	106
Revised Traffic Patterns	107
New Policies and Procedures	107
Equipment Training	107
Ongoing Support for Adult Learners	107
6. Summary	109
AAMI Survey Results—Lessons Learned	109
Conclusions	110
7. References and Resources	113
Annexes	
A Data Requirements for Functional Planning of Sterile Processing Areas	121
B Examples of Space Program Summaries for the Decontamination, Preparation and Packaging, and Sterilization Areas in a Sterile Processing Department	125
C Example of a Time Study for Sterile Processing	129
D Sample Calendar for Moving to a New SPD	133
E Infection Control Risk Assessment: Matrix of Precautions for Construction & Renovation	135
F Example of Equipment Listing by SPD Functional Area	141
G Example of an Equipment Orientation Checklist	143
Figures	
1 Example of a Spaghetti Diagram	36
2 SPD Equipment Location and Materials Flow	69
3 Contact Time vs. Temperature for Thermal Disinfection	79
4 Microbicidal Processes and Use of PPE	80
Tables	
1 IES-Recommended Illuminance Levels for Work Environments	32
2 Ventilation Requirements for Functional Areas	34
3 OSHA Permissible Noise Exposures	53
4 Addressing Worker Complaints About IEQ	54
5 Summary of Perioperative-Focused Strategies to Manage the Impact of SPD Renovation	65
6 Water Quality for Processing Devices to be Pasteurized or Thermally Disinfected. .	72
7 Water Quality for Processing Devices to be Sterilized by Steam or Low-Temperature Gas	73
8 Minimum Cycle Times for Gravity-Displacement Steam Sterilization Cycles	90
9 Minimum Cycle Times for Dynamic-Air-Removal Steam Sterilization Cycles	91
A.1 Data Requirements for Functional Planning of Sterile Processing Areas	121
B.1 Volume Projections	125
B.2 Example of a Space Program Summary for the Decontamination Area	126
B.3 Example of a Space Program Summary for the Preparation and Packaging Area and Sterilization Area	128
C.1 Example of a Time Study for Sterile Processing	129
F.1 Sample Equipment Listing by SPD Functional Area	141

Dedication:

I would like to especially thank my husband, Michael E. Hubbard, for his patience with my immersion in the creation of this book and for his ongoing support of my efforts to advance the sterile processing specialty and improve patient care outcomes.

Acknowledgments:

During the writing of these guidelines, I was very fortunate to have the assistance of several creative and forward-thinking minds. Judy Veale, as copy editor and researcher, is exceptional and brought a long and productive writing career with AAMI and other organizations to bear in creating a cohesive first-of-its kind document. Mark Duro, a dedicated sterile processing manager with first-hand renovation and construction planning experience, provided the most practical of suggestions and additions. Darren Henkel's experience as a materials manager, equipment consultant, space planner, and project manager on many SPD construction projects ensured that the discussions related to the design process were current and relevant to today's issues. The clinical expertise of consultants Rose Seavey and Cynthia Spry, as well as their willingness to share their practical knowledge, ensured that the most current infection prevention concepts were consistently applied to sterile processing issues and to meeting the needs of perioperative patient-care practitioners. Martha Young's enthusiastic support for this project and her attention to detail in ensuring that sterilization practice and equipment planning were presented in a comprehensive manner are greatly appreciated. Veteran perioperative manager Karen Stewart's assistance in reviewing these guidelines reflects a collaborative working relationship forged while we navigated the often murky planning waters encountered when developing a successful SPD/OR interface in a new construction project. Thanks to Cindy Molko, Damien Berg, Sue Klacik, and those persons and organizations that provided materials that are included in the Annexes as practical examples of planning documents. And, thanks are also due to the reviewers and guiding forces at AAMI: Steve Campbell, Erika Hatva, and their team. I thank you all for your support and professionalism.



Foreword

In 2010, AAMI members expressed interest in a comprehensive construction planning guideline for sterile processing departments (SPDs), because resources and references on this topic had not previously been organized and developed. During the writing of *Building for the Future: Construction and Renovation of Sterile Processing Facilities*, extensive research was undertaken to document principles and requirements related to the many issues. Relevant articles detailing experience with the design process and its application to construction and renovation work in sterile processing were found to be lacking in the literature searches. Consequently, recommendations on the practical application of many aspects of the planning process and ideas to enhance effective design in sterile processing have been based on the sterile processing-related work experience of the author.

Creating these guidelines has been a privilege and a pleasure and has allowed me to apply my experience both as a sterile processing manager and a consultant for SPD construction planning into a document that explores the many issues and provides planners with tools that can be used to achieve successful outcomes. During the writing process, I was reminded of the many learning opportunities I have had over the years and how these varied experiences prepared me now to analyze retrospectively what worked well and where we struggled. I am grateful for my many mentors, teachers, and colleagues who provided guidance along the way and for their special skills in contributing to the project outcomes.

From this perspective, I can emphatically state that collaborative planning, accurate data, having an eye toward the future, and ongoing, respectful communication are the keys to successful project management. Participation in planning and implementing new construction and/or SPD renovation is not commonly found in the resumes of sterile processing managers and architects. Consequently, new SPD planners and designers, although initially excited by the possibilities of a new construction project, frequently become overwhelmed by the many details and stresses of the process. In this situation, designers might lose perspective of the key operational and space needs in SPD as they interface with a lengthy process that requires flexibility, negotiation skills, and compromise.